COPC APPROVED: 11/12/2025, APP REQ #: 6381

24-HOURS AFTER A STORM EVENT GREATER THAN 0.5 INCHES. THE CONTRACTOR SHALL INSTALL A RAIN GAUGE AT THE SITE TO MONITOR AND DOCUMENT RAINFALL EVENTS IN EXCESS OF 0.5 INCHES. LOCATIONS WHERE THE SITE IS COMPLETELY CONSTRUCTED AND STABILIZED, THE AREA SHALL BE INSPECTED ONCE PER MONTH. ALL INSPECTIONS SHALL BE RECORDED ON AN INSPECTION FORM, SUCH AS THE FORM PRESENTED HEREIN. THE INSPECTIONS SHALL ENSURE THE FOLLOWING:

A. DISTURBED AREAS

ALL DISTURBED AREAS AND AREAS USED MATERIAL STORAGE SHALL BE INSPECTED FOR POLLUTANTS ENTERING THE STORMWATER SYSTEM. THE STORMWATER MANAGEMENT SYSTEM FOR EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE INSPECTED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. LOCATIONS WHERE VEHICLES ENTER AND LEAVE THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFFSITE SEDIMENT TRACKING.

B. MAINTENANCE PERFORMANCE

BASED ON THE RESULTS OF EACH INSPECTION, ALL MAINTENANCE OPERATIONS NEEDED TO ASSURE PROPER COMPLIANCE WITH THIS PLAN SHALL BE DONE IN A TIMELY MANNER, BUT IN NO CASES LATER THAN 7 DAYS FOLLOWING THE INSPECTION.

C. REPORTING REQUIREMENTS

ALL INSPECTIONS SHALL BE RECORDED ON AN INSPECTION FORM, SUCH AS THE FORM PRESENTED HEREIN. THE PERMITTEE SHALL RETAIN ALL INSPECTION REPORTS FOR A PERIOD OF 3 YEARS FROM THE DATE WHEN CONSTRUCTION IS COMPLETE OR WHEN THE SITE IS COMPLETELY STABILIZED. A COPY OF THIS PLAN SHALL BE RETAINED AT THE CONSTRUCTION SITE FROM THE DATE OF PROJECT INITIATION TO THE DATE OF FINAL STABILIZATION.

X. NON-STORMWATER DISCHARGES

IN ADDITION TO STORMWATER DISCHARGES, THIS PLAN ALSO APPLIES TO IRRIGATION RUNOFF AND RUNOFF FROM CONSTRUCTION TECHNIQUES. THIS PLAN DOES NOT APPLY TO DISCHARGES FROM FIRE FIGHTER ACTIVITIES. NO SANITARY OR INDUSTRIAL WASTES SHALL BE DISPOSED IN THE STORMWATER MANAGEMENT SYSTEM. ANY DISCHARGES OF THESE WASTES MUST BE CONTAINED, CLEANED, AND POTENTIALLY REPORTED TO THE LOCAL POLLUTION CONTROL AUTHORITY.

XI. DEWATERING

A DEWATERING PERMIT IS REQUIRED BY SOUTH FLORIDA WATER MANAGEMENT DISTRICT PRIOR TO WORK. ALL DERM PERMIT REQUIREMENTS MUST BE FOLLOWED.

PRIOR TO ANY DISCHARGE OF GROUND WATER (DEWATERING) FROM CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS PROJECT TO WATERS OF THE STATE, THE CONTRACTOR SHALL TEST THE EFFLUENT (WATER DISCHARGED) IN ACCORDANCE WITH RULE 62-621.300(2), F.A.C. IF THE TEST RESULTS ON THE EFFLUENT ARE BELOW THE SCREENING VALUES, THE CONTRACTOR SHALL SUBMIT A SUMMARY OF THE PROPOSED CONSTRUCTION ACTIVITY AND THE TEST RESULTS TO THE FDEP, WITHIN ONE (1) WEEK AFTER DISCHARGE BEGINS. THE CONTRACTOR SHALL CONTINUE TO SAMPLE THE EFFLUENT AS REQUIRED THROUGHOUT THE PROJECT AND COMPLY WITH ALL CONDITIONS OF RULE 62-621.300(2), F.A.C. IF THE GROUND WATER EXCEEDS THE SCREENING VALUES OF RULE 62-621.300(2), F.A.C., THE CONTRACTOR SHALL COMPLY WITH OTHER APPLICABLE RULES AND REGULATIONS PRIOR TO DISCHARGE OF THE EFFLUENT (GROUND WATER) TO SURFACE WATERS OF THE STATE.

CERTIFICATION STATEMENTS

ALL CONTRACTOR(S) AND SUBCONTRACTOR(S) RESPONSIBLE FOR IMPLEMENTING THIS SWPPP MUST SIGN THE FOLLOWING CERTIFICATION:

"I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND, AND SHALL COMPLY WITH, THE TERMS AND CONDITIONS OF THE STATE OF FLORIDA GENERIC PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES AND THIS STORMWATER POLLUTION PREVENTION PLAN PREPARED THEREUNDER."

NAME	COMPANY	DATE

"I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS."

NAME (OPERATOR AND/OR RESPONSIBLE AUTHORITY) DATE

INSPECTION REPORT FORM

INSPECTION FREQUENCY: WEEKLY OR AFTER 0.50 INCHES RAIN

INSTRUCTIONS: ENTER THE DATE OF THE INSPECTION. IF THE INSPECTED ITEM IS SATISFACTORY, INSERT A CHECK. IF THE INSPECTED ITEM IS UNSATISFACTORY, INSERT A "X" AND DESCRIBE THE MAINTENANCE ACTIONS TAKEN TO CORRECT THE PROBLEM. THE INSPECTOR SHALL ENTER THEIR INITIALS. CREATE ADDITIONAL SHEETS IF NECESSARY.

INSPECTION DATE	RAINFALL DATA	1. SILT FENCE	2. SWALES & BERMS	3. STORM PIPE, DRAINS & INLETS	4. INLET PROTECTION	5. BUFFERS	6. ROW DEBRIS	7. CONSTRUCTION EXIT	8. ROADS & CURBS	9. SOD, MULCH, SEED	10. OUTFALL PROTECTION	11. GEOTEXTILE PROTECTION	12. TREE PROTECTION	13. WASTE DISPOSAL	14. OTHER	OBSERVATIONS / ACTIONS	INSPECTED BY

BAR EQUALS 1" AT FULL SCALE (11"x 17")
THE OFFICIAL RECORD OD THIS SHEET IS THE ELECTRONIC FILE DIGITALLY SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.
PRELIMINARY DOCUMENTS